





300 S. DAYTON ST. DAVISON, MI 48423 PH: 810-653-9626 FAX:810-654-2616

Part Weight	1.44 lbs.	TOLE
Min/Max Temp.	-30/140 Degrees F	.X= Fro
Pressure Tested	4.3 PSI	 .Χ
Material	Flexible PVC 60 Duro Shore A	AN(
Installation Torque	60" Lbs.	UNLESS OTHE
Conforms to ASTM	D5926	
Box Quantity	10	INCHES
Clamps used	300 Series	
		3RD ANGLE

DESCRIPTION: OLERANCES: Qwik Ell 3" PVC x 3" PVC Flexible Fractional ± Elbow

 $.XX = \pm .060$ $.XXX = \pm .032$ $ANG. = \pm 0.5^{\circ}$ OTHERWISE SPECIFIED

QL-300

DESIGNER: SCALE D. Brady not to scale IGLE PROJECTION CHECKER: DATE: 4/9/2010 SHEET 1 OF 1 DO NOT SCALE DRAWING

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF FERNCO, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF FERNCO, INC. IS PROHIBITED.