





Equipped with 300SS Clamps Installation Torque 60in-lb

	Part Weight		TOLERANCES: .X= Fractional ± .XX= ±.02 .XXX=±.030	
	Min/Max Temp.	-30/140 Degrees F		
	Pressure Tested	4.3 PSI		
	Material	Flexible PVC	ANG.= ±0.5° UNLESS OTHERWISE SPECIFIED	
	Installation Torque	60" Lbs.		
	Conforms to ASTM	D5926		
	Box Quantity	40	INCHES	SIZE
	Clamps used	300 Series		/ \
			3RD ANGLE PROJECTION	

Coupling 12" West Coast Clay x 12" Plastic/Cast Iron

1002-1212WC

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF FERNCO, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF FERNCO, INC. IS PROHIBITED.

UNITS:
INCHES

A

DESIGNER:

AJD

SCALE

not to scale

3RD ANGLE PROJECTION
DO NOT SCALE DRAWING

DATE:

10/31/2014

SHEET 1 OF 1