





DESCRIPTION:

300 S. DAYTON ST. DAVISON, MI 48423 PH: 810-653-9626 FAX:810-654-2616

Equipped with 300SS Clamps Installation Torque 60in-lb

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF FERNCO, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF FERNCO, INC.

| | 9 | | IOLER | AINCES: |
|---------------|-------------|---------------------------------|----------------------------|---------------------|
| Min/Max Temp. | | -30/140 Degrees F | .X= Fractional ± | |
| Pressur | re Tested | 4.3 PSI | .XX= ±.060 .XXX=+.032 | |
| Materi | al | Flexible PVC 60 Duro Shore A | | $= \pm 0.5^{\circ}$ |
| Installa | tion Torque | 60" Lbs. | UNLESS OTHERWISE SPECIFIED | |
| Confo | rms to ASTM | D5926, C1173 | | I |

12.88 lbs.

300 Series

Part Weight

Box Quantity

Clamps used

DO NOT SCALE DRAWING

INCHES

TOLERANCES:

1002-1515WC

Coupling 15" West Coast Clay x 15" Cast Iron/Plastic

SCALE not to scale AJD 3RD ANGLE PROJECTION CHECKER: 10/31/2014 SHEET 1 OF 1